



PROALL®
A TEREX BRAND

P75

the next generation
of mobile concrete mixers



FOR MORE DETAILS
+1 855.335.9500

P75 MODEL

The P75 is a versatile and efficient concrete mixing machine that allows for on-site production, precise material measurements, and customizable batch sizes.



ADDITIONAL OPTIONS

Body

- Aggregate Bin Liner
- 360° Swivel Chute
- Aluminum Tool Box
- Aerator System for Cement Bin
- Aggregate Bin Extensions
- Pnuematic Fill with Filter Bag Assembly
- Dual Water Tank Fill

Safety

- Standard System Rear Ladder & Platform
- Cement Bin Safety Rail

Verification

- Belt Materials Sensors
- Gate Height
- Verification Sensors
- Load Cell System

Application

- Additional Vibrators
- Color Feeder
- Fiber Feeder
- Guniting Auger
- Heat Exchanger
- Additional Admix Tanks

Additional

- Pressure Washer
- Custom Paint
- Extra Oil Cooler
- Auto-Lube System

HIGHLIGHTED SPECIFICATIONS

Production Capacity	6.5m ³ / 8.5yd ³
Production Rate	50m ³ /hr (65yd ³ /hr)
Aggregate Bin	4.4m ³ / 156ft ³
Sand Bin	3.9m ³ / 139ft ³
Cement Bin	3.2m ³ / 113ft ³
Water Tank	1500L / 400gal

STANDARD FEATURES

Wireless Remote	Variable Speed Cement Metering
Automated Admix System	Automated Chain Oil
Batch Ticketing System	Automated Electric Vibrators
Electric Tarp System	
Automated Water System	



Discover more about our options and how they can improve your businesses needs.

OUR ADVANTAGE



Accuracy

Our Commander automated control system ensures accurate and consistent concrete production.



Operator Design

Commander prioritizes operator ease, offering a user-friendly interface and intuitive controls for seamless operation.



Customer Support

ProAll offers reliable customer support, providing prompt assistance for any inquiries or technical issues.

GET IN TOUCH



Sales: 1.855.335.9500
Parts: 1.855.335.9500
Support: 1.833.577.6255



Sales: ProAll.Info@Terex.com
Parts: ProAll.Parts@Terex.com
Support: ProAll.Support@Terex.com



Visit: www.Proallinc.com



P75 MODEL

The P75 is a versatile and efficient concrete mixing machine that allows for on-site production, precise material measurements, and customizable batch sizes.

Standard Features

Model	P75
Product Capacity	6.5m ³ / 8.5yd ³
Production Rate	50m ³ /hr (65yd ³ /hr)
Cement Bin	3.2m ³ / 113ft ³
Water Tank	1500 L / 400 US gal
Aggregate Bin A	4.4m ³ / 156ft ³
Aggregates Bin B	3.9m ³ / 139ft ³
Admix Tank 1	40L / 10 gal
Admix Tank 2	80L / 20 gal
Mixing Auger Diameter/Length	(228mm) 9" / (2438mm) 96"
Operator Control	Console/ Wireless
Control System	Commander
Drive	By truck PTO
Two Way Remote	On-board remote
Tarp Cover	Mesh
Delivery Printer	On-board printer
P75 Unit Length	6731mm / 265"
P75 Unit Height	2477mm / 97.5"
P75 Unit Working Swing	120 degree
P75 Unit Weight (dry weight)	*5034 kg / 11097lbs
Chain Lubrication	Automated
Water System	Automated
Vibrators	Electric
Hydraulic Pumps	High Efficiency Piston Pumps

* depending on mounting configuration

